

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-135-20748 70-07 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Ranken Energy Corporation KCC LICENSE # 3447
(owner/company name) (operator's)

ADDRESS 2325 SW 15th Street CITY Edmond

STATE Oklahoma ZIP CODE 73013 CONTACT PHONE # (316) 792-3664

LEASE Hardman "J" WELL# 1 SEC. 11 T. 18 R. 22 (S&W/West)

C - NW - SW SPOT LOCATION/QQQQ COUNTY Ness

1980 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

4620 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 338 CEMENTED WITH 250 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 4351 CEMENTED WITH 450 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Marmaton 4102-28', Miss OH 4351-55'

ELEVATION 2372/2377 T.D. 4355 PBDT 4355 ANHYDRITE DEPTH 1628
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Plug down casing as follows: 50 sx w/ 500# hulls from TD to 3750', 55 bbl heavy mud from 3750 to 1650', 150 sx from 1650' to surface, 200 sx total 60-40 poz w/ 6% gel

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? Yes

If not explain why? not available

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Thomas Larson PHONE# (316) 792-3664

ADDRESS P.O. Box 553 City/State Great Bend, Kansas

PLUGGING CONTRACTOR Halliburton Services KCC LICENSE # _____
(company name) (contractor's)

ADDRESS P.O. Box 405 Ness City, KS 67560 PHONE # (913) 798-2435

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 6-27-92

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 7-13-92 AUTHORIZED OPERATOR/AGENT: Thomas C. Larson
(signature)

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1992
07-15-1992
CONSERVATION DIVISION
Wichita, Kansas