

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-24130-00-00
Spot: SWNESE Sec/Twnshp/Rge: 21-31S-4E
1943 feet from S Section Line, 747 feet from E Section Line
Lease Name: HITTLE Well #: 3
County: COWLEY Total Vertical Depth: 3430 feet

Operator License No.: 33405
Op Name: ANSTINE & MUSGROVE INC.
Address: PO BOX 391
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2550		
CIBP	5.5	3370		
PROD	5.5	3428		600 sx cement
SURF	8.625	207		175 sx cement

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/16/2012 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: AS PER KCC RULES & REGULATIONS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 04/16/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/ TBG @ 2240', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION AND MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 2% CC AND DISPLACED IN CASING. LAYED DOWN TUBING. WAITED 2 HOURS. TAGGED CEMENT @ 1940'. RIH W/TBG @ 250', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION AND MIXED & PUMPED 58 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 4-16-2012 @ 5:00 PM. CONSOLIDATED CEMEN TICKET #34299.

Perfs:


Top	Bot	Thru	Comments
3386	3390	CSG	
3342	3346	CSG	
3328	3334	CSG	
2464	2470	CSG	

Remarks: CEMENT & SURFACE ON BACKSIDE OF 5-1/2" CASING / COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed


6/25/12 (TECHNICIAN)

RECEIVED

JUN 25 2012

KCC WICHITA
Form CP-2/3

JK