

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-23120-00-01  
Spot: S2NWSE Sec/Twnshp/Rge: 21-31S-4E  
1590 feet from S Section Line, 2104 feet from E Section Line  
Lease Name: HITTLE ESTATE Well #: 2A  
County: COWLEY Total Vertical Depth: 3363 feet

Operator License No.: 33405  
Op Name: ANSTINE & MUSGROVE INC.  
Address: PO BOX 391  
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3360		
SURF	8.625	207		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/13/2012 8:00 AM  
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.  
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (620) 441-8165

Proposed Plugging Method: AS PER KCC RULES & REGULATIONS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE  
Date/Time Plugging Completed: 04/13/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SHOT SQUEEZE HOLES @ 2000' - 2001 (2 HOLES) RIH W/ TBG @ 2000', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION AND MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 2% CC AND DISPLACED IN CASING. LAYED DOWN TUBING. WAITED 2 HOURS, TAGGED CEMENT @ 1900'. RIH W/TBG @ 250', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION AND MIXED & PUMPED 66 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 4-13-2012 @ 5:00 PM. CONSOLIDATED CEMENT TICKET # 34297.

Perfs:

Top	Bot	Thru	Comments
3286	3292	CSG	

Remarks: JUNK IN HOLE @ 2329' / CEMENT @ SURFACE ON BACKSIDE OF 5-12" CASING (335'-0') / COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed Duane Krueger  
6/28/12 (TECHNICIAN)

RECEIVED

JUN 25 2012  
Form CP-2/3

KCC WICHITA