

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20579-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 21-31S-4E
1932 feet from S Section Line, 2026 feet from E Section Line
Lease Name: HITTLE Well #: 1
County: COWLEY Total Vertical Depth: 3335 feet

Operator License No.: 33405
Op Name: ANSTINE & MUSGROVE INC.
Address: PO BOX 391
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2400		
PROD	5.5	3335		300 SXS CMT
SURF	8.625	200		150 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2012 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: AS PER KCC RULES & REGULATIONS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 04/12/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/ TBG @ 2400', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION AND MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 2% CC AND DISPLACED IN CASING. LAYED DOWN TUBING. WAITED 2 HOURS, TAGGED CEMENT @ 2100'. RIH W/TBG @ 250', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION AND MIXED & PUMPED 67 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 4-12-2012 @ 5:00 PM. CONSOLIDATED CEMENT TICKET #34295.

Perfs:

Top	Bot	Thru	Comments
2354	2360	CSG	

Remarks: CEMENT @ SURFACE ON BACKSIDE OF 5-12" CASING / COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed _____

Duane Krueger
6/25/12
(TECHNICIAN)

RECEIVED

Form CP-2/3

JUN 25 2012

KCC WICHITA