

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19096-00-00
Spot: SESWNE Sec/Twnshp/Rge: 34-33S-5E
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: BROWN Well #: 1
County: COWLEY Total Vertical Depth: 3051 feet

Operator License No.: 33118
Op Name: ANSTINE, GARY DBA ANSTINE OIL CO
Address: 27630 21ST RD
GEUDA SPRINGS, KS 67051

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3038	198	75 SX
SURF	8.625	301		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/11/2012 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLING Phone: (580) 363-3036

Proposed Plugging Method: AS PER KCC RULES & REGULATION

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 04/11/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/ TBG @ 3000', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION AND MIXED & PUMPED 75 SXS 60/40 POZMIX 4% GEL 2% CC AND DISPLACED IN CASING. LAYED DOWN TUBING. WAITED 2 HOURS, TAGGED CEMENT @ 2400'. 5-1/2" CASING PARTED @ 198', LAYED DOWN 198' OF 5-1/2" CASING. RIH W/TBG @ 350', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION AND MIXED & PUMPED 95 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 4-11-2012@ 5:00 PM. CONSOLIDATED CEMENT TICKET #34275.

Perfs:

Top	Bot	Thru	Comments
3038	3051	OH	

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)
6/28/12

RECEIVED

JUN 25 2012

Form GP-2/3

KCC WICHITA