

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-20716-00-00  
Spot: E2NWNWNW Sec/Twnshp/Rge: 19-32S-5E  
4881 feet from S Section Line, 4791 feet from E Section Line  
Lease Name: PAYNE Well #: 2  
County: COWLEY Total Vertical Depth: 2410 feet

Operator License No.: 33277  
Op Name: COOPER, ALBERT L. DBA COOPER SER  
Address: PO BOX 381  
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2400	360	75 sx
SURF	8.625	250		100 sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/12/2012 8:00 AM  
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L. DBA COOPER SERVICE CO.  
Proposal Rcvd. from: ALBERT COOPER Company: COOPER SERVICE CO Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/09/2012 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

3-12-2012, MIRU COOPER SERVICE CO, DID CELLER WORK. 3-26-2012, RIH ON WIRELINE TAGGED UP SOLID @ 1548', RIH ON WIRELINE SET PLUG @ 1450', SANDED BACK ON TOP OF PLUG @ 1400'. DUMP BAILED 5 SXS CEMENT ON TOP. RIH ON WIRELINE & CUT CASING @ 360', LAYED DOWN 9 JOINTS 5-1/2" CASING (360'), 5-9-2012, RIH W/TBG @ 300', COPELAND ACID SERVICE ESTABLISHED CIRCULATION AND MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 12:00 PM 5-9-2012. COPELAND ACID CEMENT TICKET #37909.

Perfs:


Top	Bot	Thru	Comments
2336	2372		CSG

Remarks: COMPLIANCE / 10 YR RULE / DENIED TA

Plugged through: TBG

District: 02

Signed

  
6/25/12 (TECHNICIAN)

RECEIVED Form CP-2/3

JUN 25 2012

KCC WICHITA

14