

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20628-00-00
Spot: SWSWNWSW Sec/Twnshp/Rge: 4-14S-20W
1562 feet from S Section Line, 5006 feet from E Section Line
Lease Name: KISNER Well #: 1
County: ELLIS Total Vertical Depth: 4085 feet

Operator License No.: 31240
Op Name: ENTERPRISE INC
Address: 2708 BARCLAY DR
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3962		125 SX
SURF	8.625	230		160 SX

Well Type: SWD UIC Docket No: D15659.0 Date/Time to Plug: 06/08/2012 3:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: STEVE WEILERT Company: ENTERPRISE INC. Phone: (785) 650-1952

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.
DV tool @ 1602' w/375 sx cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2012 6:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Hooked up to casing. Pumped 8 bbls to load and injected @ 3 bpm/450 #.
Mixed 100 sx cement followed w/290 sx cement w/600 # hulls.
Well on vacuum. Wait on cement.
Pumped 30 sx cement with a vacuum. Wait on cement.
Pumped 30 sx cement @ 300 psi. Shut in.
06/08/2012 checked well cement down 20' to 25'.

Remarks: QUALITY WELL SERVICE TICKET # 5530

Plugged through: CSG

District: 04

Signed: Ray Dinkel
6/28/12 (TECHNICIAN)

CM

cc to MUC 6/28/12

JUN 19 2012

RECEIVED
JUN 27 2012
KCC WICHITA

Form CP-2/3