

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-199-20152-00-01
Spot: SENWNWSW Sec/Twnshp/Rge: 6-15S-42W
2180 feet from S Section Line, 4820 feet from E Section Line
Lease Name: ARAPAHOE UNIT OWWO Well #: 110
County: WALLACE Total Vertical Depth: 5300 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 14077 CUTTEN RD PO BOX 690688
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	5300		220 SX
SURF	8.58	515		275 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/23/2012 11:00 AM
Plug Co. License No.: 32997 Plug Co. Name: EASTERN COLORADO WELL SERVICE, LLC
Proposal Rcvd. from: HERSHALL KENNEDY Company: CITATION O & G CORP. Phone: (719) 340-4637

Proposed Plugging Method: Ordered 550 sx 60/40 poz mix 4% gel cement w/500# hulls.
Plugged through tubing.
8 5/8" surface casing set @ 515' w/275 sx. 4 1/2" production casing set @ 5300' w/220 sx.
DV tool set @ 1887' w/450 sx. Total depth 5300'. Perforations: 5080'-5230'. CIBP @ 5226'. CIBP @ 5149'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/23/2012 7:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 5120'. Pumped 150 sx cement w/200 # hulls.
Pulled tubing to 2800'. Pumped 150 sx cement w/150 # hulls.
Pulled tubing to 1400'. Pumped 125 sx cement w/150 # hulls.
Pulled tubing to 700'. Pumped 65 sx mixed w/300 # hulls. Cement to surface.
Pulled tubing to surface. Topped 4 1/2" casing w/25 sx cement. Casing standing full.
Connected to 8 5/8" surface casing. Pumped 25 sx cement. Maximum pressure 400 psi.

Perfs:

Top	Bot	Thru	Comments
5080	5226		

Remarks: ALLIED CEMENT TICKET # 56,201

Plugged through: TBG

District: 04

Signed Darrel Dipman
6/28/12 (TECHNICIAN)

CM

MAY 29 2012

RECEIVED

JUN 27 2012

KCC WICHITA

Form CP-2/3