

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-001-02343-00-00
Spot: SESWNW Sec/Twnshp/Rge: 14-25S-19E
2805 feet from S Section Line, 4455 feet from E Section Line
Lease Name: SALLEE Well #: Q-17
County: ALLEN Total Vertical Depth: 904 feet

Operator License No.: 33805
Op Name: ENSMINGER OIL, LLC
Address: 1446 3000 ST
MORAN, KS 66755

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	904		40 SX
SURF	7	20		5 SX

Well Type: EOR UIC Docket No: E14357.13 Date/Time to Plug: 03/06/2011 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Revd. from: DON ENSMINGER Company: Phone: (620) 496-2300

Proposed Plugging Method: RUN 900' 1" PIPE, PUMP 50' CEMENT, PULL 1" PIPE TO 600' PUMP 50' CEMENT PULL 1" PIPE TO 250' PUMP CEMENT TO SURFACE. RUN 1" PIPE OUTSIDE OF CASEING TO 250' PUMP CEMENT TO SURFACE, PULL 1" PIPE TOP OFF CEMENT TO SURFACE.

Plugging Proposal Received By: WitnessType: NONE
Date/Time Plugging Completed 03/06/2012 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe to 900'. Circulated cement through the 1" pipe inside the 4.5" casing from 900' to 400'. Pulled 1" pipe to 400'. Circulated cement through 1" pipe inside the 4.5" casing from 400' to surface. Pulled 1" pipe and topped well off with cement. A total of 57 sacks of portland cement with 4% gel was reported used to plug this well.

Perfs:

RECEIVED

JUN 27 2012 RMD

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

(TECHNICIAN)

cc to MIC 6/28/12

RECEIVED

Form CP-2/3

JUN 27 2012

KCC WICHITA