

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-199-20136-00-00
Spot: NENENWSE Sec/Twnshp/Rge: 1-15S-43W
2515 feet from S Section Line, 1340 feet from E Section Line
Lease Name: ARAPAHOE UNIT Well #: 111
County: WALLACE Total Vertical Depth: 5300 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 14077 CUTTEN RD PO BOX 690688
HOUSTON, TX 77269

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| CIBP | | 5130 | | |
| PROD | 4.5 | 5298 | | 150 SX |
| SURF | 8.58 | 687 | | 275 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/22/2012 3:00 PM
Plug Co. License No.: 32997 Plug Co. Name: EASTERN COLORADO WELL SERVICE, LLC
Proposal Rcvd. from: HERSHALL KENNEDY Company: CITATION O&G CORP. Phone: (719) 340-4637

Proposed Plugging Method: Ordered 550 sx 60/40 pozmix 4% gel cement w/500 # hulls.
8 5/8" surface casing set @ 687' w/275 sx cement. 4 1/2" production casing set @ 5298' w/150 sx cement.
Total Depth 5300'. PBTD 5130'. Perforations: 5092'-5230'. CIBP @ 5130'.
Plugged through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/22/2012 8:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 5068'. Pumped 150 sx cement w/200 # hulls.
Pulled tubing to 3000'. Pumped 150 sx cement w/200 # hulls.
Pulled tubing to 930'. Pumped 100 sx cement w/100 # hulls.
Pulled tubing to 500'. Pumped 40 sx cement. Cement to surface.
Pulled tubing to surface. Connected to production casing. Pumped 10 sx cement.
Connect to 8 5/8" surface casing. Pumped 50 sx cement.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 5092 | 5230 | | |

Remarks: ALLIED CEMENT TICKET # 35,394

Plugged through: TBG

District: 04

Signed Darrel Dipman
6/28/12 (TECHNICIAN)

CM

MAY 20 2012

RECEIVED

JUN 27 2012

Form CP-2/3

KCC WICHITA