

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-199-20135-00-00
Spot: SENWSENE Sec/Twnshp/Rge: 1-15S-43W
3500 feet from S Section Line, 900 feet from E Section Line
Lease Name: ARAPAHOE UNIT Well #: 112
County: WALLACE Total Vertical Depth: 5300 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 14077 CUTTEN RD PO BOX 690688
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5149		
PROD	4.5	5299		150 SX
SURF	8.58	682		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/22/2012 1:00 PM
Plug Co. License No.: 32997 Plug Co. Name: EASTERN COLORADO WELL SERVICE, LLC
Proposal Rcvd. from: HERSHALL KENNEDY Company: CITATION O&G CORP. Phone: (719) 340-4637

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 16/100 # sx gel and 400 # hulls.
8 5/8" surface casing set @ 682' w/250 sx cement. 4 1/2" production casing set @ 5299' w/150 sx cement.
DV tool @1953' w/360 sx. Total Depth 5300'. PBTD 5149'. Perforations: 5078'-5292'. CIBP @ 5149'.
Top down plug. Low fluid level.

Plugging Proposal Received By: CASE MORRIS WitnessType: PARTIAL
Date/Time Plugging Completed: 05/22/2012 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Connected to 4 1/2" production casing. Pumped 50 sx cement w/200 # hulls. Followed w/16 sx gel and 105 sx cement mixed w/200 # hulls. Maximum pressure 1500 psi.
Connected to 8 5/8" surface casing. Pumped 50 sx cement. Maximum pressure 300 psi

Perfs:

Top	Bot	Thru	Comments
5078	5292		

Remarks: ALLIED CEMENT TICKET # 35,393

Plugged through: CSG

District: 04

Signed

Darrel Dipman
6/28/12

(TECHNICIAN)

CM

MAY 29 2012

RECEIVED Form CP-2/3

JUN 27 2012

KCC WICHITA