

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-091-22468-00-00
Spot: NWSWNWNW Sec/Twnshp/Rge: 29-14S-22E
4524 feet from S Section Line, 4822 feet from E Section Line
Lease Name: RED DRAGON OIL Well #: 33-I
County: JOHNSON Total Vertical Depth: 917 feet

Operator License No.: 34262
Op Name: ROBERTS, LELIA M
Address: PO BOX 421
OLATHE, KS 66051

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	907		130 SX
SURF	7	22		6 SX

Well Type: EOR UIC Docket No: E25485.6 Date/Time to Plug: 03/15/2012 12:00 PM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: BILL GAUDERN Company: ROBERTS, LELIA M Phone: (785) 229-5682

Proposed Plugging Method: RUN 1" INSIDE 2 7/8" TO BELOW PERFORATIONS; FILL 2 7/8" FROM BOTTOM TO TOP. PULL 1" OUT AND TOP OFF WITH CEMENT.

Plugging Proposal Received By: JOHN ALMOND Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/15/2012 9:00 AM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Perfs:

RAN 1" PIPE DOWN TO 850' AND FILLED THE WELL FULL OF CEMENT. HOOKED ON TO 2 7/8" CASING AND SQUEEZED THE WELL. TOTAL AMOUNT OF CEMENT USED WAS 30 SACKS.

Top	Bot	Thru	Comments
846	856		

RECEIVED

JUN 27 2012 TCH

KCC Chanute Dist. #3

Remarks: THIS WELL WAS PLUGGED DUE TO A FAILED MIT.

Plugged through: TBG

District: 03

Signed

Taylor Herman

(TECHNICIAN)

cc to UIC 6/28/12

RECEIVED

JUN 27 2012

KCC WICHITA