

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-03421-00-00  
Spot: NESESE Sec/Twnshp/Rge: 16-9S-19W  
990 feet from S Section Line, 330 feet from E Section Line  
Lease Name: CASEY Well #: 1  
County: ROOKS Total Vertical Depth: 3535 feet

Operator License No.: 5010  
Op Name: KNIGHTON OIL COMPANY, INC.  
Address: 1700 N WATERFRONT PKY BLDG 100  
WICHITA, KS 67206

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 5.5   | 3530       |             | 125 SX   |
| SURF   | 8.625 | 195        |             | 100 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/12/2012 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: KEN WERNER Company: KNIGHTON OIL CO. INC. Phone: (785) 623-8516

Proposed Plugging Method: Ordered 320 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Can't get down past 3207'.  
Squeezed dakota at 1360'.  
Casing leak at 1786'-1800', 100'-130'.  
Casing leak at 2990' w/150 sx cement, 400' w/100 sx cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/12/2012 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2375'. Pumped 200 sx cement w/300 # hulls.  
Pulled tubing to 1116'. Pumped 90 sx cement w/100 # hulls.  
Pulled all tubing. Topped off 5 1/2" casing w/20 sx cement.  
Hooked to 8 5/8" x 5 1/2" annulus. Pumped 1/4 bbl and pressured to 250 psi.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3530 | 3535 |      |          |

Remarks: QUALITY WELL SERVICE TICKET # 5486

Plugged through: TBG

District: 04

Signed

Pat Bedore  
(TECHNICIAN)

CM

JUN 18 2012

RECEIVED Form CP-2/3

JUN 27 2012

KCC WICHITA