

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01824-00-00
Spot: NENWSE Sec/Twnshp/Rge: 36-10S-21W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: TRICO UNIT WEST Well #: 109
County: GRAHAM Total Vertical Depth: 3731 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3696		
PROD	5.5	3722		175 SX
SURF	8.625	240		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/13/2012 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOEL STULL Company: VESS OIL Phone: (785) 483-9169

Proposed Plugging Method: DV @ 1629' w/600 sx cement
Production perfs: 3568'-3634'.
CIBP @ 3696'.
Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/13/2012 9:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3550'. Allied pumped 150 sx cement w/400 # hulls.
Pulled tubing to 2015'. Pumped 125 sx w/400 # hulls
Pulled tubing to 1007'. Pumped 45 sx. Circulated with cement.
PTOH. Topped 5 1/2" casing off w/45 sx cement.
Hooked up to backside. Instant 800 psi.

Perfs:

Top	Bot	Thru	Comments
3722	3731		
3568	3634		

Remarks: ALLIED TICKET # 56143

Plugged through: TBG

District: 04

Signed


6/28/12
(TECHNICIAN)

CM

JUN 18 2012

RECEIVED
JUN 27 2012
KCC WICHITA

Form CP-2/3