

1 070354

MAY 29 1987

API NUMBER 15-135-20,388 -00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE SW, SEC. 7, T 19 S, R 21 W/E

660 feet from S section line

3300 feet from E section line

Lease Name Dewald Well # 1

County Ness 140.60

Well Total Depth 4326 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 288

TECHNICIAN'S PLUGGING REPORT

Operator License # 5088

Operator: John J. Darrah, Jr.

Name & Address 412 East Douglas, Suite One

Wichita, KS 67202

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 2:15 p.m. Day: 29 Month: 5 Year: 19 87

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 4312' Open hole Elevation 2218' KB Anhydrite 1450'

1st plug sand back to 4250' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1/2 sx hulls and plug, and

150 sx cement.

Plugging Proposal Received by Don C. Ubel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:15 p.m. Day: 29 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4250' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 900 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED Reserve this plugging.

DATE 6-3-87

INV. NO. 17130
5-29

Signed Dan Jordan (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
06-02-1987
JUN 2 1987
CONSERVATION DIVISION
WICHITA, KANSAS