

MAY 29 1987

To: 1 070355  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-20,432-00-00  
C NW SW, SEC. 7, T 19 S, R 21  
1980 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5088  
Operator: John J. Darrah, Jr.  
Name & Address: 412 East Douglas, Suite One  
Wichita, KS 67202

Lease Name Dewald Well # 3  
County Ness 140.01  
Well Total Depth 4308' feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 288

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111  
Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 4 p.m. Day: 29 Month: 5 Year: 19 87

Plugging proposal received from Deacon Pulley  
(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 4300' Open hole Elevation 2198' KB Anhydrite 1455'  
1st plug sand back to 4250' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1/2 sx hulls and wiper plug,  
and pump 150 sx cement.

Plugging Proposal Received by Don C. Ubel (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5 p.m. Day: 29 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4250' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 150 sx cement.

Maximum pressure 800 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form)

I hereby certify that I have observed this plugging.

DATE 6-3-87

Signed Dan Goodson (TECHNICIAN)

INV. NO. 17128

5-29

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 2 1987  
06-02-1987  
Wichita, Kansas