

To: 1 070169
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6875

Operator: Marmik Oil Company
Name & Address: 200 N. Jefferson
El Dorado, AR 71730

API NUMBER 15- 135-23,020-00-00
100' S
E/2 NW, SEC. 12, T 19 S, R 21 W BK
3860 feet from S section line
3300 feet from E section line

Lease Name Wunder Well # 1

County Ness 140.56

Well Total Depth 4325' feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 327

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Mallard Drilling License Number 4630

Address P. O. Box 905, McPherson, KS 67460

Company to plug at: Hour: 7:15 am Day: 19 Month: April Year: 19 86

Plugging proposal received from Arnie Hess

(company name) Mallard (phone) 316-241-4640

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2194'
Anhydrite 1437'

1st plug at 1470' with 50 sx cement

2nd plug at 700' with 75 sx cement

3rd plug at 360' with 40 sx cement

4th plug from 30' to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 11:00 am Day: 19 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1470' with 50 sx cement, 2nd plug at 700' with 75 sx cement, 3rd plug at 360' with 40 sx cement, 4th plug from 40' to surface with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

Tagged Cheyenne plug at 530' - Waited on cement from 8:15 to 10:35 am

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (If necessary) observe this plugging.

DATE APR 29 1986

INV. NO. 13591
4-19

Signed Dan Durrant
(TECHNICIAN)

FILED
STATE CORRELATION COMMISSION
APR 29 1986
04-28-1986
CONSERVATION DIVISION
Wichita, Kansas

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date April 10, 1986
month day year

API Number 15- 135-23,020-00-00

OPERATOR: License # ~~6878~~ 6875
 Name Marmik Oil Company
 Address 200 N. Jefferson
 City/State/Zip Eldorado, Arkansas 71730
 Contact Person Lee B. Shobe
 Phone 303-623-5842

100' S E/2 NW 12 19 21 East
 3860 Sec. Twp. S. Rg. West
 3300 Ft. from South Line of Section
 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 660 feet
 County Ness

CONTRACTOR: License # 4630
 Name Mallard Drilling
 City/State McPherson, Kansas *****

Lease Name Wunder Well # 1
 Ground surface elevation 2194 feet MSL

Well Drilled For: Well Class: Type Equipment:
 Oil SWD Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes no
 Municipal well within one mile: yes no

Depth to bottom of fresh water 240
 Depth to bottom of usable water 600 650

If OWWO: old well info as follows:

Surface pipe by Alternate: 1 2
 Surface pipe planned to be set 300'

Operator
 Well Name
 Comp Date Old Total Depth

Conductor pipe required N/A
 Projected Total Depth 4500 feet

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 4/7/86 Signature of Operator or Agent James G. Hess Title Agent

For KCC Use:

Conductor Pipe Required _____ feet; Minimum Surface Pipe Required _____ feet per Alt. 2
 This Authorization Expires 10-7-86 Approved By 4-7-86

*** please send copy of approved intent to: 412 E. Douglas, Suite One, Wichita, Kansas 67202 rather than McPherson office. Thank you

4-10-86 moucin 320' of S.P.
 4-11-86 Spud

100' S.C.E/2 NW Sec. 12 Twp. 19 S, Rg. 21 West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Arbuckle, if penetrated

1st plug @ more than 50' feet depth with 25	sxs of 60/40 pozmix, 6% gel.
2nd plug @ Anhydrite / Base feet depth with 50	sxs of same
3rd plug @ B./Cheyenne feet depth with 75	sxs of same
4th plug @ surf - 30 below surf pipe feet depth with 40	sxs of same
5th plug @ No solid bridge feet depth with _____	sxs of _____
(2) Rathole with circ cement from 40-30' to surf	(b) Mousehole with 10 sxs
15sx rathole	

PUSHER	TD	FORMATION	COMPLETION TIME & DATE
Arnie Hess			
SURFACE PIPE	8 5/8 @ 327		
ANHYDRITE	1437 ELEVATION 2202		
STARTING TIME & DATE	1468		
1st PLUG @ 1470 FT. W/ 50 SX			
2nd PLUG @ 2200 FT. W/ 75 SX			
3rd PLUG @ 360 FT. W/ 40 SX			
4th PLUG @ 30-0 FT. W/ 10 SX			
RAT HOLE CIRCULATED W/ 10 SX			
MOUSE HOLE CIRCULATED W/ 10 SX			
WATER WELL PLUGGED W/ Head - SX			
CEMENT COMPANY			
TECHNICIAN			

Alaparden co.
 25
 1/2 w
 5 into.

STATE CONSERVATION COMMISSION
 APR 28 1986
 04-28-1986
 CONSERVATION DIVISION
 Wichita Kansas