

1 051792

3-23

API NUMBER 15-135-21,960-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE SW SW, SEC. 21, T 7, R 19 S, R 21 W/XX  
330 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9615

Lease Name Meyer Well # 1

Operator: Joe Gerstner Oil Company  
Name: RR 1, Box 115A  
Address: Ness City, KS 67560

County Ness 144.17

Well Total Depth 4436 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 568

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 23 Month: 3 Year: 1994

Plugging proposal received from Pat Gerstner

(company name) Joe Gerstner Oil Co. (phone) 913-798-2893

Wells: 4 1/2" at 4432' w/275 sx cement, PBD 4434', Perfs at 4398-4406, 4418-21'

1st plug sand back to 4350' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 5 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 175 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:45 p.m. Day: 23 Month: 3 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 4 sx cement on top of sand

through bailer,

2nd plug pumped 300 lbs. hulls, 5 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 175 sx cement. Maximum pressure 100 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1100' of 4 1/2" casing. If additional description is necessary, use BACK of this report.

INVOICED

I (did / ~~XXXXXX~~) observe this plugging.

DATE 3-30-94

WELL NO 40196

Signed Richard M. Lacey (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION MAR 28 1994 CONSERVATION DIVISION Wichita, Kansas