

1 120905

3-22

API NUMBER 15- 135-22,320-00-00

To: STATE CORPORATION COMMISSION CONSERVATION DIVISION - PLUGGING SECTION E/2 NE SW SW, SEC. 21, T 7 S, R 21 W/4
200 COLORADO DERBY BUILDING WICHITA, KANSAS 67202

1155 feet from S section line

4125 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9615

Lease Name Meyer Well # 2

Operator: Joe Gerstner Oil Co.

County Ness 144.30

Name & Address RR 1, Box 115A

Well Total Depth 4440 feet

Ness City, KS 67560

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 568

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 22 Month: 3 Year: 19 94

Plugging proposal received from Pat Gerstner

(company name) Joe Gerstner Oil Co. (phone) 913-798-2893

logs: 4 1/2" at 4439' w/100 sx cement, Perfs at 4404-08, 4322-26, 4144-48, 3814-18'

1st plug sand back to 3765' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 50 sx cement at 1500-1350',

3rd plug pump 80 sx cement at 700',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:40 p.m. Day: 22 Month: 3 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 3765' and dumped 4 sx cement on top of sand

through bailer,

2nd plug at 1500-1350' with 50 sx cement,

3rd plug at 700' with 80 sx cement,

4th plug at 40' with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

MAR 28 1994 03-128-1994

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2400' of 4 1/2" casing. (If additional description is necessary, use BACK of this report.)

INVOICED

observe this plugging.

Signed Duane Rankin (TECHNICIAN)

DATE 3-30-94

INV. NO. 40197