

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-205-01081-0000
 Spot: SE/SW/SE Sec 10 Twp 29 S Rng 15 ☒ E / ☐ W
296 Feet from ☐ N / ☒ S Line of Section
1414 Feet from ☒ E / ☐ W Line of Section
 GPS: Lat: 37.503083 Long: 95.747650 Date: _____
 Lease Name: VAUGHN (WORRELL) Well #: VAU 07
 County: Wilson Total Vertical Depth: 625 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>					
Address 1: <u>130 S MARKET</u>					
Address 2: _____					
City: <u>WICHITA</u>					
State: <u>KS</u> Zip Code: <u>67202</u> - _____					

Well Type: OG - Oil & Gas UIC Docket No.: _____ Date/Time to Plug: 9/15/11 / _____
 Plug Co License No.: 33749 Plug Co. Name: KWS
 Proposal Revd from: RAMBO Company Name: KWS Phone: (620) 431-9212

Proposed Plugging Report: OPEN WELL TOP AND INVESTIGATE. RUN SWEDGE PRIOR TO WASHING TO CHECK FOR PIPE IN HOLE. IF NO PIPE WASH TO TD AND PUMP CEMENT TO SURFACE.

Plugging Proposal Received By: TONY ANDERSON Witness Type: PART - Partial
 Date/Time Plugging Completed: 9/16/11 / _____ KCC Agent: TONY ANDERSON
 Actual Plugging Report: _____ Perfs: _____ Top _____ Bottom _____ Thru _____

CUT OFF TOP TO REMOVE CEMENT PLUG. RAN 8" SWEDGE TO 400' TO CHECK FOR OBSTRUCTIONS. WASHED TO 630' AND PUMPED 1 LOAD OF CEMENT. THE NEXT DAY RAN IN TO 105' TO TAG CEMENT AND FILLED THE REST TO THE TOP, 299 SACKS OF CEMENT WERE USED. THE LOCATION WAS THEN RESTORED.

KANSAS CORPORATION COMMISSION
 OCT 01 2011
 RECEIVED

Remarks: CONTRACT:20110070- 007 ;PO#14300-0000000745; REGULAR SECTION

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: ☐ Yes ☐ No

District: 03

Tony Anderson

(Technician)

Form: District Plugging Report - _____