

12-7

RECEIVED  
KANSAS CORPORATION COMMISSION

2-

DEC 14 1993  
12-14-93  
CONSERVATION DIVISION  
WICHITA, KS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-035-21,983-0201  
SW NW SW, SECTION 24 TOWNSHIP 33 RANGE 5E

OPERATOR LICENSE # 5120 1880 FEET FROM S SECTION LINE  
4855 FEET FROM E SECTION LINE

OPERATOR RANGE OIL COMPANY  
NAME & 125 N MARKET STE 1120  
ADDRESS WICHITA KS 67202

LEASE NAME: EDDIE #2  
COUNTY: COWLEY  
WELL TOTAL DEPTH: 3132'

CONDUCTOR PIPE: \_\_\_\_\_  
SURFACE CASING: 8-5/8" @ 170'

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL  SMD \_\_\_\_\_ D&A \_\_\_\_\_  
OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: RANGE OIL COMPANY  
ADDRESS: 125 N MARKET STE 1120 WICHITA KS 67202 LICENSE: 5120

COMPANY TO PLUG AT: HOUR: 11:00 DAY: 7 MONTH: 12 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: DISTRICT #2  
COMPANY NAME: DANIELS REDIMIX PHONE: 316-221-9060

WERE: DUMP GRAVEL DOWN 4-1/2" FROM 3132' UP TO 3025' - SPOT  
4 SX CMT @ 3025' - FILL 4-1/2" W/WATER - BAIL DWN TO  
250' - DUMP CMT SLURRY FROM 250' TO SURF

PLUGGING PROPOSAL RECEIVED BY: GILBERT FINLEY

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( \_\_\_\_\_ ) PART ( X ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 1330 DAY: 7 MONTH: 12 YEAR: 1993

ACTUAL PLUGGING REPORT:  
DUMPED GRAVEL DWN 4-1/2" CSG & FILLED IT FROM 3132'  
TO 3025' - SPOTTED 4 SX CMT @ 3025' - FILLED CSG WITH  
WATER - BAILED DWN TO 250' & DUMPED CMT SLURRY FROM  
250' TO SURFACE

REMARKS: DANIELS #36708 30 SX CEMENT SLURRY

INVOICED I DID OBSERVE THIS PLUGGING.

DATE 12-30-93

NO. 39619

15/  
JERRY CLARK (AGENT)

aw

12-7