

2-050408

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

8-22

15-035-21178-00-01

API NUMBER: ~~15-035-21178-E-22-193-00-01~~

C, SW, SW, SECTION 24 TOWNSHIP 33 RANGE 05E

OPERATOR LICENSE # 5120

660 FEET FROM S SECTION LINE

4620 FEET FROM E SECTION LINE

OPERATOR RANGE OIL COMPANY  
NAME & 125 N. MARKET, SUITE #1120  
ADDRESS WICHITA, KS 67202

LEASE NAME: EDDIE #1  
COUNTY: CL Cowley  
WELL TOTAL DEPTH: 3144' 102.18

PIPE: 4 1/2" @ 3143'

SURFACE CASING: 8 5/8" @ 158'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: RANGE OIL COMPANY

ADDRESS: 125 N. MARKET, SUITE #1120, WICHITA, KS 67202 LICENSE: \_\_\_\_\_

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 22 MONTH: 8 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: DISTRICT #2

COMPANY NAME: UNITED CEMENTING PHONE: 316-321-4680

WERE: SAND BACK AND SPOT 4 XS. CMT. @ 2900'. SET BRIDGE PLUG @ 260'. RUN 1" PIPE TO 250' AND CIRCULATE CMT. TO SURFACE. PULL PIPE OUT OF HOLE AND TOP OFF WITH CMT.

PLUGGING PROPOSAL RECEIVED BY: ALAN NATION


PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 11:00 DAY: 22 MONTH: 8 YEAR: 1995

ACTUAL PLUGGING REPORT:  
SANDED BACK AND SPOTTED 4 XS. CMT. @ 2900'. 4 1/2"  
CASING CEMENTED FROM 230' TO SURFACE. SET BRIDGE PLUG @  
260'. RAN 1" PIPE TO 250' AND CIRCULATED CMT. TO  
SURFACE. PULLED PIPE OUT OF HOLE AND TOPPED OFF WITH  
CMT.

REMARKS: UNITED # 1286. 27 XS. CMT. 60/40 POZ. 2% GEL.

I DID OBSERVE THIS PLUGGING.

  
\_\_\_\_\_  
Jerry Clark (AGENT)

FORM CP-2/3  
REV. 3/90

RECEIVED  
KANSAS CORPORATION COMMISSION

INVOICED  
DATE 9-7-95  
INV. NO. 43633

SEP 06 1995  
9-6-95  
CONSERVATION DIVISION  
WICHITA KS

aw