

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23800-00-00  
Spot: SWNESWSW Sec/Twnshp/Rge: 31-15S-14W  
730 feet from S Section Line, 850 feet from W Section Line  
Lease Name: BETTY RADKE A Well #: 1-31  
County: RUSSELL Total Vertical Depth: 1636 feet

Operator License No.: 3293  
Op Name: RUSSELL OIL, INC.  
Address: PO BOX 8050  
EDMOND, OK 73083

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	916		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/20/2012 12:00 AM  
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.  
Proposal Rcvd. from: BILL SANDERS Company: SOUTHWIND DRILLING, INC. Phone: (620) 617-0706

Proposed Plugging Method: Ordered 185 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.  
Twisted off. Left 7 drill collars in hole. Top of collars @ 1425'.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE  
Date/Time Plugging Completed: 05/20/2012 8:15 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @1400 w/25 sx  
2nd plug @975 w/40 sx  
3rd plug @375 w/80 sx  
4th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

District: 04

Signed

Cory Morris  
6/05/12 (TECHNICIAN)

RECEIVED  
MAY 23 2012  
KCC WICHITA

MAY 21 2012