

WELD IN PROD. DEPT.
5/25/12

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01609-00-00
Spot: NESWSW Sec/Twnshp/Rge: 3-9S-19W
990 feet from S Section Line, 4290 feet from E Section Line
Lease Name: ROSTICAL 'B' Well #: 2
County: ROOKS Total Vertical Depth: 3426 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3424		150 SX
SURF	10.75	318		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/18/2012 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: LENNY DINKEL Company: CONSOLIDATED OIL WELL SERVI Phone: (785) 259-1928

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Squeeze jobs: 761'-792', 1068'-1360' w/250 sx, 1096'-1129' w/150 sx.
Ran 4 1/2" casing 0'-3398'.
Production Perforations: Open hole 3423'-3427', 2954'-2956' and 3081'-3083'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/18/2012 10:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Consolidated Oil Well Services pumped 230 sx w/500 # hulls. Maximum pressure 500 psi.
Shut in pressure 300 psi.
Hooked up to backside. Pumped 5 sx cement. Maximum pressure 300 psi. Shut in pressure 300 psi.

Perfs:

Top	Bot	Thru	Comments
3366	3370		
3350	3352		
3336	3340		
3328	3330		
3310	3314		
3232	3240		
3224	3226		
3210	3218		
3190	3194		
3172	3180		
3081	3083		
2954	2956		

Remarks: CONSOLIDATED OIL WELL SERVICES TICKET # 34530

Plugged through: CSG

RECEIVED
MAY 23 2012
KCC WICHITA

District: 04

Signed Richard Williams
5/18/12 (TECHNICIAN)

CM

MAY 21 2012