

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-173-20982-00-01  
Spot: E2NESE Sec/Twnshp/Rge: 14-29S-1E  
1980 feet from S Section Line, 330 feet from E Section Line  
Lease Name: CHARLES Well #: 2-14  
County: SEDGWICK Total Vertical Depth: 3500 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3225		
COND	13.375	80		125 SX
PKR		3115		
PROD	4.5	3494	959	150 SX
SURF	8.625	296		200 SX
TI	2.375	3115		

Well Type: OIL UIC Docket No: D30079.0 Date/Time to Plug: 04/02/2012 10:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: GEORGE RAYL Company: GRESSEL OILFIELD SERVICES, LL Phone: (620) 960-1288

Proposed Plugging Method: SAND BACK ABOVE PERFS TO 3090' AND CAP W/4SX, THEN RUN UP TO 350' AND SHOOT PERFS. CIRC. BACK SIDE WITH CEMENT TO SURFACE.

Plugging Proposal Received By: DAN FOX Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/03/2012 4:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

DUMPED SAND DOWN PRODUCTION CASING TO ACHIEVE 50' ABOVE PERFORATIONS AND CAPPED W/4 SXS OF CEMENT. RAN WIRE LINE DOWN AND TAGGED TOP OF CEMENT @ 3100'. OPERATOR SHOT OFF PRODUCTION CASING AT 2535' AND PULLED 4.5" PRODUCTION CASING. RAN 1" TUBING DOWN TO 365' AND CIRC. CEMENT TO SURFACE W/115 SXS. OPERATOR WILL COME BACK AND TOP OFF IF NEEDED AND CUT OFF SURFACE CASING 4' BELOW GROUND SURFACE, THEN GRADE AREA. CEMENT TICKET #32812.

Perfs:

Top	Bot	Thru	Comments
3146	3180	CSG	

Remarks: WELL WAS PLUGGED BECAUSE OF NON-PRODUCTION AND BEYOND 10YR T/A LIMITATION.

Plugged through: TBG

District: 02

Signed

Daniel R. Fry  
4/3/12 (TECHNICIAN)

KCC WICHITA

RECEIVED  
MAY 24 2012