

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20363-00-00
Spot: S2S2N2SE Sec/Twnshp/Rge: 1-10S-20W
1600 feet from S Section Line, 1320 feet from E Section Line
Lease Name: SUTOR A Well #: 15
County: ROOKS Total Vertical Depth: 3770 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3761		
PROD	4.5	3762		175 SX
SURF	8.625	209		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/22/2012 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 567-8104

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Stage collar @1648' w/350 sx.
2 7/8" tubing cemented @ 3752' w/169 sx cement.
Pump stuck in hole @ 75'. Milled beside pump to 96' and lost circulation.
Operator tried overshot and mill to remove pump. Could only get 1/2 of pump out of hole.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/22/2012 10:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 4 1/2" casing. Pumped 30 sx cement to circulate 8 5/8" x 4 1/2" annulus to surface. Closed annulus and pumped 320 sx cement w/500 # hulls. Maximum pressure 600 psi. Shut in pressure 300 psi.

Perfs:

Top	Bot	Thru	Comments
3762	3778		

Remarks: SWIFT SERVICES TICKET # 21754

Plugged through: CSG

District: 04

Signed

Pat Bedore
4/05/12 (TECHNICIAN)

CM

RECEIVED

MAY 29 2012

KCC WICHITA

Form CP-2/3

MAY 23 2012