

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20630-00-00  
Spot: SWNWSWNW Sec/Twnshp/Rgc: 12-1S-27W  
1650 feet from N Section Line, 330 feet from W Section Line  
Lease Name: SATER Well #: 1-12  
County: DECATUR Total Vertical Depth: 3685 feet

Operator License No.: 31660  
Op Name: ROBUCK, DON E. DBA ENERGY SEAR  
Address: PO BOX 31697  
AURORA, CO 80041

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 4.5   | 3685       |             | 625 SX   |
| SURF   | 8.625 | 342        |             | 255 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/21/2012 9:30 AM  
Plug Co. License No.: 31660 Plug Co. Name: ROBUCK, DON E. DBA ENERGY SEARCH OPERATING COMPANY  
Proposal Rcvd. from: BRETT D. ROBUCK Company: ENERGY SEARCH OPERATING CO. Phone: (308) 345-7200

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Perforations: 3298'-3300', 3340, 3372', 3420', 3444'-3448', 3642'-3646' and 3658'-3659'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/21/2012 2:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3000'. Pumped 160 sx cement w/500 # hulls.  
Pulled tubing to 1197'. Pumped 80 sx cement to circulate to surface.  
Pulled all tubing. Topped off 4 1/2" casing w/15 sx cement.  
Hooked to 8 5/8" x 4 1/2" annulus. Pumped 60 sx cement. Maximum pressure 200 psi. Shut in pressure 100 psi.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3658 | 3659 |      |          |
| 3642 | 3646 |      |          |
| 3444 | 3448 |      |          |
| 3420 |      |      |          |
| 3372 |      |      |          |
| 3340 |      |      |          |
| 3298 | 3300 |      |          |

Remarks: SWIFT SERVICES TICKET # 21371

Plugged through: TBG

District: 04

Signed

Pat Bedore  
6/25/12  
(TECHNICIAN)

CM

MAY 23 2012

RECEIVED Form CP-2/3

MAY 29 2012

KCC WICHITA