

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22033-00-00
Spot: S2N2NW Sec/Twnshp/Rge: 24-12S-21W
4290 feet from S Section Line, 3960 feet from E Section Line
Lease Name: HAMBURG Well #: AA-1
County: TREGO Total Vertical Depth: 4000 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1688		50 SX
PROD	5.5	3998		175 SX
SURF	8.625	203		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/21/2012 10:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: _____ Company: QUALITY OIL WELL CEMENTING Phone: (785) 483-1071

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
DV tool @ 1688' w/350 sx cement.
Perforations: 3968'-3969', 3961'-3965'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/21/2012 11:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto casing. Pumped 75 sx cement w/200 # hulls followed w/12 sx gel, followed w/225 sx cement and 300 # hulls. Shut in pressure 1000 psi.
Tied onto back side. Full shut in @ 1000 psi.

Perfs:

Top	Bot	Thru	Comments
3969	3970		
3961	3965		

Remarks: QUALITY OILWELL CEMENT TICKET # 424

Plugged through: CSG

District: 04

Signed _____

Marvin Mills
6/25/12 (TECHNICIAN)

CM

RECEIVED

MAY 29 2012

Form CP-2/3

MAY 22 2012

KCC WICHITA