

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23258-00-00
Spot: SESESE Sec/Twnshp/Rge: 19-11S-18W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: FRISBIE TWIN Well #: 2-M
County: ELLIS Total Vertical Depth: 3850 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3652		
PROD	5.5	3849		200 SX
SURF	8.625	321		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/18/2012 9:30 AM
Plug Co. License No.: 34272 Plug Co. Name: OUTLAW WELL SERVICE LLC
Proposal Rcvd. from: KEN Company: TRANS PACIFIC OIL CORP. Phone: (316) 262-3596

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/700 # hulls.
Perforation @ 1725', 1425' and 800'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/18/2012 9:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3200'. Pumped 125 sx cement w/300 # hulls.
Pulled tubing to 2500'. Pumped 125 sx cement w/200 # hulls.
Pulled tubing to 1400'. Pumed 110 sx cement w/200 # hulls.
Cement circulated.
POOH. Hooked up to casing. Pumped 155 sx cement @ 300⁺ psi.
Braden head dug out and found to be full of cement.

Perfs:

Top	Bot	Thru	Comments
3659	3666		
3639	3646		
3614	3626		

Remarks: QUALITY CEMENTING TICKET # 661

Plugged through: TBG

District: 04

Signed

Ray Dinkel
6/15/12

(TECHNICIAN)

CM

MAY 22 2012

RECEIVED

MAY 29 2012

KCC WICHITA