

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21009-00-00
Spot: NENESW Sec/Twnshp/Rge: 32-8S-27W
2266 feet from S Section Line, 3100 feet from E Section Line
Lease Name: MOSIER Well #: 3
County: SHERIDAN Total Vertical Depth: 4301 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		3642		
PROD	4.5	4314		550 SX
SURF	8.625	251		200 SX
TI	2.375	3642		

Well Type: SWD UIC Docket No: E26379.1 Date/Time to Plug: 05/17/2012 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Packer stuck in hole w/188'. Stem sticking up.
Perforations @ 3694', 3711', 3748'-3754', 3778', 3787'-3792', 3836', 3865', 3877', 3900'-3905', 4270'.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/17/2012 12:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3403'. Pumped 90 sx cement w/300 # hulls.
Pulled tubing to 2900'. Pumped 90 sx cement w/200 # hulls.
Pulled tubing to 1500'. Pumped 125 sx cement. Good circulation.
Tied onto casing. Squeezed w/25 sx cement. Shut in pressure 400 psi.
Tied onto back side. Squeezed w/ 40 sx cement. Shut in pressure 100 psi.

Perfs:

Top	Bot	Thru	Comments
4270			MISSISSIPPI
3902			
3900	3905		
3877			
3865			
3836			
3790			
3788			
3787	3792		
3752			
3748	3754		
3711			LKC
3694			TORONTO

Remarks: CONSOLIDATED CEMENT TICKET # 34538

Plugged through: TBG

District: 04

Signed

[Handwritten Signature]
[Handwritten Date: 5/17/12]

(TECHNICAL) RECEIVED

CM

MAY 21 2012

MAY 29 2012

Form CP-2/3

KCC WICHITA