

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20629-00-00
Spot: S2NENW Sec/Twnshp/Rge: 10-13S-19W
990 feet from N Section Line, 1980 feet from W Section Line
Lease Name: MERMIS Well #: 2
County: ELLIS Total Vertical Depth: 3738 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3723		150 SX
SURF	8.625	230		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/23/2012 10:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: ART SCHOENHOFER Company: PROFESSIONAL PULLING SERVIC Phone: (316) 267-4214

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
DV tool @1384' w/300 sx.
Perforations: 3362'-3474'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/23/2012 1:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3300'. Pumped 150 sx cement w/250 # hulls.
Pulled tubing to 1800'. Pumped 180 sx cement w/200 # hulls.
Pulled tubing out. Topped off w/35 sx cement full.
Tied onto back side. Pumped 10 sx cement. Shut in pressure 300 psi.

Perfs:

Remarks: CONSOLIDATED CEMENT TICKET # 34534

Plugged through: TBG

District: 04

Signed  (TECHNICIAN)

CM

MAY 24 2012

RECEIVED

Form CP-2/3

MAY 29 2012

KCC WICHITA