

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-20754-00-01  
Spot: SWNENW Sec/Twnshp/Rge: 8-17S-27W  
996 feet from N Section Line, 1657 feet from W Section Line  
Lease Name: JOHNSON Well #: 1  
County: LANE Total Vertical Depth: 4597 feet

Operator License No.: 3842  
Op Name: LARSON ENGINEERING, INC. DBA LAR  
Address: 562 W STATE RD 4  
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4145		
PROD	5.5	4577	0	WITH 150 SX CMT
SURF	8.625	402		WITH 225 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/23/2012 10:00 AM  
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.  
Proposal Rcvd. from: TOM LARSON Company: LARSON ENGINEERING Phone: (620) 653-7368

Proposed Plugging Method: SPOT 30 SX CMT & 200# HULLS ON BOTTOM. 30 SX CMT AT 2140'. FILL CASING 1350' TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/23/2012 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

\*\*THE WELL HAS BEEN SQUEEZED FROM 3198-3541' W/100 SX CMT, 3146-3197' W/50 SX CMT, 1467-1650' W/300 SX CMT.\*\* CIBP @ 4145'. TBG IN HOLE FROM 4100' TO 1700'. TRIED TO WASH OVER COULD NOT MAKE ANY HEADWAY. WORKED ON FOR 1 1/2 DAYS. RUN TBG TO 1676' & PUMPED 180 SX CMT & 500# HULLS. CMT DID CIRCULATE. PULLED TBG & PUMPED 25 SX CMT. CASING STAYED FULL. TIED ONTO BACKSIDE & PUMPED 1/4 BBL & PRESSURED TO 500#. HELD.

Perfs:

Top	Bot	Thru	Comments
4549	4553		
4534	4537		
4533	4536		
4468	4474		
4384	4388		
4266	4268		
4230	4232		
4229	4231		
4168	4170		
4161	4163		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

RECEIVED  
MAY 29 2012

District: 01

Signed Michael Maier  
6/13/12 (TECHNICIAN)

KCC WICHITA

RECEIVED

MAY 24 2012

KCC DODGE CITY

MAIER