

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-08545-00-00
Spot: E2NWSESW Sec/Twnshp/Rge: 9-15S-13W
990 feet from S Section Line, 3349 feet from E Section Line
Lease Name: ROESNER Well #: 5
County: RUSSELL Total Vertical Depth: 3062 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 380 SOUTHPOINTE BLVD #130
CANONSBURG, PA 15917

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	40		15 SX
PROD	7	3036		100 SX
SURF	13	484		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2012 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: KIM HOFFMAN Company: EMPIRE ENERGY E&P, LLC Phone: (620) 282-7893

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/500 # hulls and 13 sx gel.
Perfs: 1425', 840', 400'.
20" and 13" casing was dug out and found to be full of cement.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2012 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2923'. Pumped 6 sx gel pressured up in tubing and displaced out of tubing.
Pulled tubing to 2766'. Pumped 100 sx cement w/200 # hulls.
Pulled tubing to 1992'. Pumped 7 sx gel.
Pulled tubing to 1648'. Pumped 100 sx cement w/200 # hulls.
568' pumped 85 sx cement.
Cement circulated.
POOH. Hooked to casing and pumped 20 sx cement @ 300 psi. Shut in.

Perfs:

Top	Bot	Thru	Comments
3036	3062		ohio
2979	2986		ohio
2908	2914		ohio

Remarks: QUALITY CEMENTING TICKET # 845

Plugged through: TBG

District: 04

Signed

Ray Dinkel
7/10/12

(TECHNICIAN)

KCC WICHITA

CM

JUN 22 2012