

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19178-00-02
Spot: NESWSESW Sec/Twnshp/Rge: 9-15S-13W
332 feet from S Section Line, 3386 feet from E Section Line
Lease Name: ROESNER Well #: 11
County: RUSSELL Total Vertical Depth: 3361 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 380 SOUTHPOINTE BLVD #130
CANONSBURG, PA 15917

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3331		300 SX
SURF	10.75	631		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/05/2012 8:30 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELLL SERVICE, INC.
Proposal Revd. from: KIM HOFFMAN Company: EMPIRE ENERGY E&P, LLC Phone: (620) 282-7893

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/700 # hulls and 13 sx gel. Perf: 1425', 840', and 400'.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/06/2012 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2923'. Pumped 13 sx gel followed w/100 sx cement w/300 # hulls.
Pulled tubing to 1491'. Pumped 100 sx cement w/200 # hulls.
Pulled tubing to 838'. Pumped 75 sx cement w/100 # hulls.
Pulled tubing to 404'. Pumped 80 sx cement.
Cement circulated.
POOH. Hooked up to casing and pumped 10 sx cement @ 300 psi. Shut in. Hooked to Braden head and pumped 10 sx of cement @ 400 psi. Shut in over night

Perfs:

Top	Bot	Thru	Comments
3056	3092		
2988	2994		
2414	2419		
2403	2407		

Remarks: QUALITY CEMENTING TICKET # 971

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel
7/10/12

(TECHNICIAN)

CM

RECEIVED
JUL 02 2012
KCC WICHITA

JUN 22 2012