

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-30256-00-01  
Spot: W2NESW Sec/Twnshp/Rge: 6-13S-17W  
1980 feet from S Section Line, 1650 feet from W Section Line  
Lease Name: STAAB A Well #: 4  
County: ELLIS Total Vertical Depth: 2770 feet

Operator License No.: 5145

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	145		100 sx

Op Name: DREILING OIL INC

Address: 1008 CODY AVE PO BOX 550  
HAYS, KS 67601

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/23/2012 7:00 PM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Revd. from: TERRY PIESKER

Company: EXPRESS WELL SERVICE & SUPPL Phone: (785) 735-2289

Proposed Plugging Method: Ordered on 06/23/2012, 150 sx 60/40 pozmix 4% gel cement. Ticket # 56437  
Ordered on 06/25/2012, 305 sx 60/40 pozmix 4% gel cement and 15 sx gel.  
06/20/2012-Express Well Service moved in and ran 7 7/8" bit drilled to 2770'.  
On 06/23/2012 lost circulation. Marvin Mills had operator pump 150 sx cement and pull tubing at 7:00pm.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/25/2012 12:00 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:


06/25/2012-Express Well ran in hole with tubing. Tagged cement @ 2025'. Allied rigged to tubing and mixed and pumped 15 sx gel followed by 10 sx cement.  
Pulled tubing to 1800'. Allied rigged to tubing and mixed and pumped 30 sx cement.  
Pulled tubing to 1300'. Allied rigged to tubing and mixed and pumped 30 sx cement.  
Pulled tubing to 725'. Allied rigged to tubing and mixed and pumped 200 sx to circulate cement to pit area. Pulled tubing. Topped off 8 5/8" casing with 35 sx. Hole standing full.  
This well was drilled out and re-plugged due to a nearby UIC application.

Remarks: ALLIED OIL AND GAS LLC TICKET # 56438

Plugged through: TBG

District: 04

Signed

  
7/10/12

(TECHNICIAN)

CM

JUN 26 2012

RECEIVED  
JUL 02 2012  
KCC WICHITA