

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24956-00-00
Spot: SWNWNENE Sec/Twnshp/Rge: 35-20S-11W
4913 feet from S Section Line, 1203 feet from E Section Line
Lease Name: MILLER NORTH Well #: 1-35
County: BARTON Total Vertical Depth: 3420 feet

Operator License No.: 34110
Op Name: CAERUS KANSAS LLC
Address: 600 17TH ST, STE 1600 N
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7.875	3419		175 SX
SURF	8.625	515		350 SX
TI	2.375	3386		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/18/2012 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: BRIAN KARLIN Company: CAERUS KANSAS LLC Phone: (785) 623-3290

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/18/2012 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations. Topped w/5 sx cement at 3003'.
Cut casing off at 2435'.
Pulled casing to 1200'. Pumped 100 sx cement w/200 # hulls.
Pulled casing to 950'. Pumped 70 sx cement w/100 # hulls.
Pulled casing to 450'. Pumped 140 sx cement w/100 # hulls.
Pulled casing to 225'. Circulated cement to surface w/70 sx cement.
Pulled casing. Hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3324	3327		
3317	3327		
3302	3335		
3090	3189		

Remarks: QUALITY WELL SERVICE

Plugged through: CSG

District: 04

Signed Bruce Rodie
7/10/12 (TECHNICIAN)

RECEIVED
JUL 02 2012
KCC WICHITA

CM

JUN 20 2012