

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-14545-00-00
Spot: S2SWSE Sec/Twnshp/Rge: 14-20S-11W
330 feet from S Section Line, 1980 feet from E Section Line
Lease Name: ZAHORSKY H Well #: 5
County: BARTON Total Vertical Depth: 3274 feet

Operator License No.: 4184
Op Name: CASINO PETROLEUM, LLC
Address: PO BOX 415
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3218		
PROD	5.5	3268		70 SX
SURF	8.625	182		70 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/15/2012 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CHRIS BATCHMAN Company: CASINO PETROLEUM Phone: (620) 564-2517

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix gel cement.
Operator did not have liner information on CP-1. Operator ran liner in well from top to bottom and circulated cement.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/15/2012 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 492'.
Ran tubing to 3000'. Pumped 100 sx cement.
Pulled tubing to 1500'. Pumped 50 sx cement.
Pulled tubing to 750'. Circulated cement to surface w/50 sx cement.
Pulled tubing. Tied to casing. Pumped 10 sx cement pressured to 200 psi. Shut in.

Perfs:

Top	Bot	Thru	Comments
3198	3202		LANSING
3090	3094		LANSING

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie
7/10/12

(TECHNICIAN)

RECEIVED
JUL 02 2012
KCC WICHITA
CM

JUN 25 2012