

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03520-00-00
Spot: N2NESE Sec/Twnshp/Rge: 18-16S-13W
2310 feet from S Section Line, 660 feet from E Section Line
Lease Name: LUERMAN Well #: 3
County: BARTON Total Vertical Depth: 3392 feet

Operator License No.: 30705
Op Name: YOUNGER ENERGY COMPANY
Address: 453 S WEBB RD STE 100
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3384		
SURF	10.75	81		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/25/2012 7:45 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: DON BROWNING Company: YOUNGER ENERGY CO Phone: (785) 810-8230

Proposed Plugging Method: Ordered 225 sx 60/40 pozmix 4% gel cement, 9 sx gel, 400 # hulls.
Squeezed @ 400'-430' w/175 sx, 510' w/100 sx and 2183'-2612' w/225 sx.
Open hole arbuckle shut off w/ CIPB @ 3383' and 28 gal of resen cement on top.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/25/2012 7:45 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3070'. Pumped 9 sc gel followed w/75 sx cement w/150 # hulls.
Pulled tubing to 1412'. Pumped 75 sx cement w/150 # hulls.
Pulled tubing to 673'. Pumped 55 sx cement.
Cement circulated.
POOH. Hooked to casing and pumped 15 sx cement @ 300 psi.
Braden head was dug out and found to be full of cement from a squeeze job in 1994.

Perfs:

Remarks: ALLIED CEMENTING TICKET # 65153

Plugged through: TBG

District: 04

Signed Ray A. Dinkels
7/16/12 (TECHNICIAN)

CM

RECEIVED
JUL 02 2012
KCC WICHITA

Form CP-2/3

JUN 26 2012