

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03035-00-00
Spot: SESESE Sec/Twnshp/Rge: 12-9S-19W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: HILGERS Well #: 1
County: ROOKS Total Vertical Depth: 3475 feet

Operator License No.: 34179
Op Name: THOMAS M. BROWN LLC
Address: PO BOX 250
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	13	230		175 SX
	11 5.5	3473		
PROD	5.5	3472		250 SX
SURF	8.625	1350		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/25/2012 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Revd. from: JAKE BROWN Company: THOMAS M BROWN Phone: (785) 737-7070

Proposed: Alt 1 -1350' w/350 sx.
Plugging: 12-17-2004 squeezed 8 5/8" x 5 1/2" annulus w/200 sx common cement.
Method: Cement 4 1/2" liner to 2680' w/150 sx circulated w/cement.
Arbuckle open hole completion 3472'-3475'. Unknown perforations in LKC
Ordered 475 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/25/2012 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Operator ran 4 1/2" packer to 2640' and pumped 150 sx cement. Pulled packer.
Ran tubing back in to 2640'. Quality pumped 100 sx w/300 # hulls. Pulled tubing to 1320'.
Quality pumped 80 sx cement. Circulated cement.
PTOH. Topped off casing w/15 sx. Casing full.
Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
3472	3475		OPEN HOLE

Remarks: QUALITY OIL WELL CEMENTING

Plugged through: TBG

District: 04

Signed Richard Williams
7/1/12 (TECHNICIAN)

RECEIVED
JUL 02 2012
KCC WICHITA

JUN 26 2012