

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21981-00-00
Spot: SENENWSW Sec/Twnshp/Rge: 24-16S-16W
2225 feet from S Section Line, 1125 feet from W Section Line
Lease Name: RUDY Well #: 1-24
County: RUSH Total Vertical Depth: 3681 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	855		350 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/29/2012 7:30 PM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: RANDY MARTIN Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: 1ST PLUG AT 3578' WITH 50 SX CMT. 2ND PLUG AT 890' WITH 50 SX CMT. 3RD PLUG AT 450' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE
Date/Time Plugging Completed: 06/29/2012 9:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

1ST PLUG AT 3578' WITH 50 SX CMT. 2ND PLUG AT 980' WITH 50 SX CMT. 3RD PLUG AT 450' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTERS.

Plugged through: DP

District: 01

RECEIVED
JUL - 5 2012
KCC DODGE CITY

Signed Stephen J Pfeifer
(TECHNICIAN)

RECEIVED
JUL 09 2012
KCC WICHITA

Form CP-2/3

Handwritten initials