

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-21073-00-01  
Spot: N2S2NWSW Sec/Twnshp/Rge: 28-30S-33W  
1775 feet from S Section Line, 663 feet from W Section Line  
Lease Name: HICKMAN C Well #: 4  
County: HASKELL Total Vertical Depth: 4989 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		3015		
PROD	5.5	4989	0	WITH 515 SX CMT
SURF	8.625	1608		WITH 485 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/19/2012 10:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 250# HULLS & 25 SX CMT INTO PERFS. PLUG AT 3050' WITH 25 SX CMT. PLUG AT 1750' WITH 30 SX CMT. PLUG AT 700' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/19/2012 12:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

\*\*CEMENT CIRCULATED TO SURFACE IN 5 1/2" CASING WHEN WELL WAS COMPLETED\*\* PUMP 250# HULLS & 25 SX CMT INTO PERFS. 1ST PLUG AT 3050' WITH 25 SX CMT. 2ND PLUG AT 1750' WITH 30 SX CMT. 3RD PLUG AT 700' WITH 30 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. PUMP 5 SX CMT INTO 8 5/8" X 5 1/2" ANNULUS. PRESSURED TO 350 PSI.

Perfs:

Top	Bot	Thru	Comments
4805	4810		
4782	4790		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: TBG

District: 01

RECEIVED  
JUN 27 2012  
KCC DODGE CITY

Signed

Jack MacLaskey  
(TECHNICIAN)

RECEIVED  
JUL 09 2012  
KCC WICHITA

Form CP-2/3

*BWZ*