

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-20580-00-01  
Spot: SWNW Sec/Twnshp/Rge: 36-34S-35W  
1980 feet from N Section Line, 660 feet from W Section Line  
Lease Name: KINNEY CHESTER SAND UNIT Well #: 801S  
County: STEVENS Total Vertical Depth: 6800 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4130		
COND	20	40		WITH 5 SX CMT
PROD	5.5	6794	2020	WITH 175 SX CMT
SURF	8.625	1659		WITH 775 SX CMT

Well Type: WSW UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/27/2012 1:30 PM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT AT PERFS. PLUG AT 1690' WITH 50 SX CMT. PLUG AT 590' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/27/2012 4:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMP 200# HULLS & 25 SX CMT AT 3450'. 1ST PLUG CIRCULATED HOLE WITH GEL & PUMPED 50 SX CMT AT 1690'. 2ND PLUG AT 590' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6541	6543		
6527	6535		
4130	4130		
3550	3550		
3450	3480		

Remarks: USED COMMON CEMENY BY SARGENT LILLARD.

Plugged through: CSG

District: 01

RECEIVED  
JUL - 3 2012  
KCC DODGE CITY

Signed

Jack MacLaskey  
(TECHNICIAN)

RECEIVED  
JUL 09 2012  
KCC WICHITA

Form CP-2/3