

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24803-00-00  
Spot: NWNWSENW Sec/Twnshp/Rge: 34-20S-14W  
1400 feet from N Section Line, 1400 feet from W Section Line  
Lease Name: COTTER Well #: 1-34  
County: BARTON Total Vertical Depth: 3702 feet

Operator License No.: 5056  
Op Name: F. G. HOLL COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3640		
PROD	5.5	3702		200 SX
SURF	8.625	834		335 SX
TI	2.375	3625		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/21/2012 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ROB LONG Company: F G HOLL Phone: (620) 793-0915

Proposed Plugging Method: Ordered 320 sx 60/40 pozmix 4% gel cement w/500 # hulls

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/21/2012 12:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations. Topped w/5 sx cement.  
Cut casing at 2425'.  
Pulled casing to 1450'. Tied to casing. Pumped 125 sx cement w/400 # hulls.  
Pulled casing to 840'. Pumped 75 sx cement w/100 # hulls.  
Pulled casing to 500'. Pumped 75 sx cement.  
Pulled casing to 200'. Circulated cement w/50 sx cement.  
Pulled casing. Hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3364	3368		
3321	3368		

Remarks: QUALITY WELL SERVICE

Plugged through: CSG

District: 04

Signed Bruce Rodie  
7/10/12 (TECHNICIAN)

JUN 26 2012

RECEIVED  
JUL 09 2012  
KCC WICHITA

Form CP-2/3