

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-23201-00-00  
Spot: N2N2SE Sec/Twnshp/Rge: 5-21S-14W  
2310 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: DEBES A Well #: 1-5  
County: STAFFORD Total Vertical Depth: 2715 feet

Operator License No.: 5056  
Op Name: F. G. HOLL COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2713	801	WITH 150 SX CMT
SURF	8.625	856		WITH 335 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/27/2012 3:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK 50' ABOVE PERFS & 5 SX CMT ON TOP OF SAND BRIDGE. PLUG AT 880' WITH 15 SX GEL & 50 SX CMT. PLUG AT 220' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/27/2012 6:35 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

\*\*UNABLE TO FIND COLLAR BELOW 801' DUE TO RATTY PIPE. JUNK LEFT IN HOLE = 35' OF CABLE TOOLS, 1350' OF 5/8" SAND LINE, SPEAR & CHANGE OVER SUB, & 4' OF 2 3/8" TBG ON TOP OF SPEAR\*\* SAND TO 2290' & 50 SX CMT. 1ST PLUG AT 801' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 227' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2340	2348		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed

*Stephen J. Pfeifer*  
3/10/12  
TECHNICIAN

RECEIVED  
JUL - 5 2012  
KCC DODGE CITY

RECEIVED  
JUL 09 2012  
KCC WICHITA

Form CP-2/3

POWY