

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-02832-00-00
Spot: NWSENE Sec/Twnshp/Rge: 28-14S-14W
4296 feet from S Section Line, 398 feet from E Section Line
Lease Name: OLSON A J - B Well #: 3
County: RUSSELL Total Vertical Depth: 3280 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 380 SOUTHPOINTE BLVD #130
CANONSBURG, PA 15917

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3149		320 SX
SURF	8.625	620		400 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/29/2012 8:30 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.
Proposal Rcvd. from: RICK POPP Company: EMPIRE ENERGY E&P, LLC Phone: (620) 282-7893

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement, 7 sx gel and 300 # hulls.
Perforations: 400', 800' and 1400'.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/29/2012 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2950'. Pumped 7 sx gel followed w/75 sx cement w/150 # hulls.
Pulled tubing to 1450'. Pumped 150 sx cement w/100 # hulls.
Cement circulated out the backside.
POOH. Hooked to casing and pumped 130 sx cement.
Cement circulated out the braden head. Shut in.

Perfs:

Top	Bot	Thru	Comments
3207	3212		
3050	3068		
3007	3010		

Remarks: QUALITY CEMENTING TICKET # 4715

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel
7/10/12

(TECHNICIAN)

CM

JUN 29 2012

RECEIVED
JUL 09 2012
KCC WICHITA

Form CP-2/3