

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20653-00-00
Spot: NWENWSW Sec/Twnshp/Rge: 24-29S-25W
2584 feet from S Section Line, 941 feet from W Section Line
Lease Name: DOUBLE H FARMS Well #: 24-1
County: FORD Total Vertical Depth: 5471 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5245		WITH 2 SX CMT
PC		1505		225 SX
PROD	5.5	5468	0	WITH 175 SX CMT
SURF	8.625	780		WITH 350 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/03/2012 12:30 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Revd. from: THAD STARR Company: AMERICAN ENERGIES Phone: (620) 793-2146

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT OR CIBP WITH 2 SX CMT. PLUG AT 1600' WITH 25 SX CMT. PLUG AT 600' WITH 25 SX CMT. PLUG AT 60' WITH 10 SX CMT. BRING 20 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/03/2012 2:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5245' WITH 2 SX CMT. 1ST PLUG AT 1632' WITH 25 SX CMT WITH 50# HULLS. 2ND PLUG AT 605' WITH 25 SX CMT. 3RD PLUG CIRCULATED CMT TO SURFACE FROM 90' WITH 45 SX CMT. TOPPED OFF WITH 5 SX CMT. PRESSURED BACKSIDE TO 100# WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5390	5396		
5309	5396		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT**USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED

JUL - 5 2012

KCC DODGE CITY

Signed



(TECHNICIAN)

RECEIVED

JUL 09 2012

KCC WICHITA

Form CP-2/3

