

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21311-00-00
Spot: E2NW Sec/Twnshp/Rge: 36-31S-32W
1296 feet from N Section Line, 2030 feet from W Section Line
Lease Name: JACOBS Well #: 2-36
County: SEWARD Total Vertical Depth: 5929 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5460		WITH 2 SX CMT
DVT		3092		WITH 370 SX CMT
PROD	4.5	5808	1351	WITH 220 SX CMT
SURF	8.625	1682		WITH 725 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/22/2012 9:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: STEVE EMICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: CIBP @ 5460' WITH 2 SX CMT. PLUG AT 3130' WITH 20 SX CMT. PLUG AT 1730' WITH 20 SX CMT. IF PULLING CASING, PUT 50 SX CMT AT 560' & 10 SX CMT AT 40'. IF NO CASING PULLED, PERFORATE CASING @ 500' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: PARTIAL
Date/Time Plugging Completed: 06/22/2012 1:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

RAN CBL SHOWING TOC @1500 SET CIBP @ 5460' WITH 2 SX CMT. 1ST PLUG AT 3130' WITH 20 SX CMT. 2ND PLUG AT 1730' WITH 20 SX CMT. 3RD PLUG AT 1340' WITH 50 SX CMT. 4TH PLUG AT 560' WITH 50 SX CMT. 6TH PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5518	5527		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED

JUN 27 2012

KCC DODGE CITY

Signed

Jack MacLaskey
7/10/12
(TECHNICIAN)

RECEIVED

JUL 09 2012

KCC WICHITA

Form CP-2/3

ADW