

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19141-00-01
Spot: SENEENW Sec/Twnshp/Rge: 2-28S-4E
4685 feet from S Section Line, 2954 feet from E Section Line
Lease Name: AMBLER Well #: 5
County: BUTLER Total Vertical Depth: 2625 feet

Operator License No.: 5446
Op Name: GILES, BENJAMIN M.
Address: 346 S. LULU
WICHITA, KS 67211

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2210		
SURF	8	1820		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/07/2012 8:00 AM
Plug Co. License No.: 34231 Plug Co. Name: M & S WELL SERVICE, LLC
Proposal Rcvd. from: DUSTY Company: BENJAMIN M GILES Phone: (316) 265-1992

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND OR CEMENT @ 2020, CAP W/5 SXS CEMENT. PERF @ 250', CIRCULATE BETWEEN CASINGS TO SURFACE.

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/15/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE W/BAILOR TO TD. LAYED DOWN BAILOR. SANDED BACK @ 2020'. 3-14-2012, TAGGED SAND @ 2020', DUMP BAILED 5 SXS CEMENT ON TOP. DUG OUT CELLER & CUT WINDOW IN 7" CASING, NO CEMENT @ SURFACE. 3-15-2012, RIH ON WIRELINE SHOT SQUEEZE HOLES @ 250'-251', 4 SHOTS PER FT. RIH W/TBG @ 250', COPELAND ACID SERVICE MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL 3% CC AND DISPLACED IN CASING. SDON. 3-16-2012, RIH W/TBG @ 325', DID NOT TAG CEMENT. PULLED TBG @ 250', COPELAND ACID MIXED & PUMPED 40 SXS CLASS A 3% CC AND DISPLACED IN CASING. WAITED 2 HRS, RIH W/TBG @ 250', COPELAND ACID MIXED & PUMPED 40 SXS CLASS A 3% CC AND DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 250'. RIH W/TBG @ 245', COPELAND ACID SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 145 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. PLUG DOWN, 5:00 PM 3-15-2012. COPELAND ACID CEMENT TICKET #32805. PUMPED TOTAL 325 SXS W/200# HULLS. 4-26-2012. TAGGED CEMENT @ 212', RIH W/1" TBG @ 210', COPELAND ACID SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 40 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. 5-3-2012, TAGGED CEMENT @ SURFACE. 6-20-2012, CUT CASINGS BELOW GROUND LEVEL, & FILLED PIT. P & A COMPLETE.

Perfs:

Top	Bot	Thru	Comments
2072	2078		CSG

RECEIVED
JUL 10 2012
KCC WICHITA

Remarks: COMPLIANCE / 10 YEAR TA
Plugged through: TBG

District: 02

Signed *Duane Krueger*
3/15/12 (TECHNICIAN)