

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19531-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 26-28S-5E
4232 feet from S Section Line, 2490 feet from E Section Line
Lease Name: NORTH FOX BUSH Well #: 15
County: BUTLER Total Vertical Depth: 2802 feet

Operator License No.: 32475
Op Name: BRADEN, JAMES R. DBA BRADEN PET
Address: 10139 SW HAVERHILL RD
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2737		
SURF	15.5	375		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/25/2012 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: JAMES BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 222-1252

Proposed Plugging Method: ACCORDING TO KCC RULES AND REGULATIONS.

Plugging Proposal Received By: DUANE KRUEGER
Date/Time Plugging Completed: 06/25/2012 5:00 PM

Witness Type: PARTIAL
KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK 50' ABOVE PERFS @ 2685', DUMP BAILED 6 SXS CEMENT ON TOP. RIH ON WIRELINE LINE SHOT SQUEEZE HOLES (4 SHOTS) @ 250'-251'. RIH W/TBG @ 250', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 261 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 6-25-2012, 5:00 PM. CONSOLIDATED CEMENT TICKET #36212.

Perfs:

Top	Bot	Thru	Comments
2742	2802	OH	OPEN HOLE

Remarks: LANDOWNER COMPLAINT/ 10 YEAR

Plugged through: TBG


RECEIVED

JUL 10 2012

KCC WICHITA

District: 02

Signed


7/10/12
(TECHNICIAN)

JK