

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19533-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 24-28S-5E
257 feet from S Section Line, 4784 feet from E Section Line
Lease Name: NORTH FOX BUSH Well #: 12
County: BUTLER Total Vertical Depth: 2849 feet

Operator License No.: 32475
Op Name: BRADEN, JAMES R. DBA BRADEN PET
Address: 10139 SW HAVERHILL RD
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2802	250	110 SX
SURF	8.625	105		60 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/25/2012 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: JAMES BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 222-1252

Proposed Plugging Method: ACCORDING TO KCC RULES AND REGULATIONS.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/25/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK 50' ABOVE PERFS @ 2750', DUMP BAILED 4 SXS CEMENT ON TOP. CUT CASING @ 250', LAYED DOWN 8 JOINTS 4-1/2" CASING (250'). RIH W/TBG @ 250', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 80 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 6-25-2012, 5:00 PM. CONSOLIDATED CEMENT TICKET #36211.

Perfs:

Top	Bot	Thru	Comments
2802	2849	OH	OPEN HOLE

Remarks: LANDOWNER COMPLAINT/ 10 YEAR


Plugged through: TBG

RECEIVED

JUL 10 2012

KCC WICHITA

District: 02

Signed 
(TECHNICIAN)